
Canberra Airport Taxiway Bravo Extension

Tim Jackson

Specialist Products & Services Manager

Downer EDI





Australian Pavement Recycling and Stabilisation Conference

Pavement Recycling for Sustainable Roads

Novotel Brighton Beach, Sydney • 10th August 2022



Downer





Australian Pavement Recycling and Stabilisation Conference

Pavement Recycling for Sustainable Roads

Novotel Brighton Beach, Sydney • 10th August 2022

Introduction

Client: Canberra Airport

Project: Taxiway Bravo Extension

Location: Canberra, ACT

Commencement: October 2019

Completion: July 2020

Design Consultant: GHD

Downer Capability:

Ex Situ Foam Bitumen
Stabilisation & Placement

Asphalt Production & Placement





Project Overview

- The northern extension of Taxiway Bravo at Canberra Airport, allows the efficient operation of the Canberra Airports main Runway 17/35
- The project consists of 1.5kms of new pavement and associated infrastructure
- Pavement construction adjacent to runway, consisting of lean mix concrete subbase and foam bitumen stabilised base with asphalt wearing course







Downer Delivery

- Production & placement of Foam Bitumen Stabilised (FBS) Crushed Rock, using mobile KMA220 Pugmill (Under Curfew) 2 x layers to form 250mm layer thickness
- Installation & removal of temporary ramps during FBS programme (Under Curfew)
- Cutback Bitumen Prime coat application to all crushed rock base on aircraft pavements and associated shoulders
- Cold milling & Tie-in to existing interfaces at Runway17/35, TWY Bravo, TWY Foxtrot & TWY Delta
- Production, delivery & placement of asphalt from fixed asphalt production facility, Hume ACT







The task at hand









Key Facts

- Mobilisation & Establishment of KMA Pugmill from Qld to Canberra Airport
- Source local Aggregate supplier
- Establish Mix Design with 100% virgin crushed graded 20mm fine crushed rock
- Ex-Situ Production Foam Bitumen Base (FBB), using mobile KMA220 Pugmill (Under Curfew/Night shift)
- Ex-situ placement (by paver) of FBB in 2 x
 layers to form 250mm overall layer thickness
 Average 385t placed per Shift

Key Plant	Wirtgen KMA 220 Mobile Pugmill (Foamed Bitumen) Vogele Super 1800-3 Tracked Paver
Pavement Level Control	Paveset Level Control
Expedient Pavement	7,300m2 TWY Echo & TWY Foxtrot
Material	4,600t Foam Bitumen Stabilised Crushed Rock
Working Shifts	12no.







Establishment









KMA Plant Set up











Removal of Temporary Ramps









Delivery











Taxiway Echo



Australian Pavement Recycling and Stabilisation Conference

Pavement Recycling for Sustainable Roads

Novotel Brighton Beach, Sydney • 10th August 2022





Taxiway Foxtrot














Vogele Super 1800-3 Tracked Paver









Taxiway Foxtrot







Time Lapse - Shift 11 Footage courtesy of Canberra Airport & Huon Contractors

Activity	Detail	Start	Finish	Comment	Run No	Start Run	Finish Run	Tonnes per Run	Prog. Tonnes (inc. wastage)	Comments
Toolbox Meeting	Site Compound	14:00	14:30	FBS Production Team	Actual					
	Site Compound	22:00	22:45	FBS Placement Team & Subbies.	1	01:00	01:16	67	67	TWY Foxtrot - Layer 2 - Straight Runs
Security Checks	твс	22:45	23:15		2	01:26	01:42	67	135	TWY Foxtrot - Layer 2 - Straight Runs
Site Handed Over		23:45	0:00	WSOs to place U/S Cones	3	01:52	02:08	67	202	TWY Foxtrot - Layer 2 - Straight Runs
Establish on Site		0:00	0:10	Establish light towers and traffic management	4	02:18	02:34	67	269	TWY Foxtrot - Layer 2 - Straight Runs
Cut Ramp & Proof Roll		0:10	1:00	Use Front-End Loader and 2 Rigids	5	02:44	03:00	67	336	TWY Foxtrot - Layer 2 - Straight Runs
Prep Site	Sweeping	1:00	1:30		6	03:10	03:26	67	404	TWY Foxtrot - Layer 2 - Straight Runs
Survey	Set Out & Mark Paving Runs	0:30	2:08		7	03:36	03:52	67	471	TWY Foxtrot - Layer 2 - Straight Runs
FBS Laying TWY Foxtrot		1:00	3:52	Long straight runs, thus large volume FBS FCR						
Compaction		1:20	4:30	Excl. Temp Ramps Compaction	Temporary Ramp				р	
Testing	In-Situ Tests	3:00	4:45			-		0		RWY Adjacent - Static Roll
Surveying	Finish surface pick up	1:52	4:45			-	•	0		Longitudinal - Static Roll
Temp Ramp	Laying & Static Roll (FCR)	3:36	4:00				04:30	Finish Rolling of Placed FBS (excl. Ramps)		
	Bitumen Emulsion	4:00	4:20				125	Average Thickness (mm)		
Site Cleanup	0:15	4:30	4:45				0	Paving Tonnes (excl. Ramps)		
Final FOD Check	0:15	4:45	5:00				Stockpile	Paving Tonnes/hour		
Site Handed Back		5:00					varies	Run Length (m)		



Australian Pavement Recycling and Stabilisation Conference

Pavement Recycling for Sustainable Roads

Novotel Brighton Beach, Sydney • 10th August 2022













Project Challenges

- Most significant challenges was completing the works within the short night curfew of 00: 00 to 05:00
- Removal & Installation of temporary ramps (Select Fill & FBB) to maintain compliance to MOS 139, each shift
- Technical specification required the FBB to be constructed in a total thickness of 250mm, but no greater than a single 200mm layer thickness
- Paving the Taxiway Shapes
- Inclement weather experienced during the FBB programme
- Managing the daily deliveries of ex-situ raw materials in a restricted area. Also, managing bitumen & lime deliveries Ex-Sydney







Key Outcomes

- Placement of Ex-Situ FBB by paver provided consistent layers of the required thickness, uniform density and without segregation. Also avoided the disturbance to underlying layers
- Paver placement of FBB materials, enabled efficient planning of the shifts in a small working window, minimising quality issues and maximising waste control
- The use of paving equipment with pre-compaction devices i.e. vertical oscillating tamper blades, maximises initial compaction at placement, therefore, enabling optimum productivity each shift
- The use of level control system ensured a single paved run & efficient compaction No trimming required
- The works completed on time and within budget, No incidents or MTI's or LTI's recorded
- Post FBB works, Downer successfully delivered all 14mm A10E Asphalt works approx. 12,000t







Conclusion

- Foam bitumen stabilisation process, has provided improved strength of the granular materials while retaining a flexible pavement in critical aircraft turning locations
- Through the use of Foamed Bitumen Stabilisation at TWY Echo & TWY Foxtrot, the expedient pavement will
 exhibit superior fatigue properties, which will result in a benefit for whole of life costs for Canberra Airport
- This project demonstrates that Ex-situ Foam Bitumen Stabilisation is a viable pavement solution and method, working within the constraints of an operational airfield environment









Thank you





